



**Connect Well No. 18 to EWTF Raw Water Main
Improvements
City of Chino
Chino, CA**



Project Type

Domestic Water Pipeline Conveyance

Project References

Jesus Plasencia
City of Chino
(909) 464-0781

Steven Andrews Engineering prepared construction drawings and specifications for the installation of 1,050 lineal feet of 12-inch C900 PVC water main along Euclid Avenue for the City of Chino within street right of way. The project included connecting to the existing water well no. 18 outlet pipe, reconnecting existing fire hydrant laterals, and connecting to an existing 18" PVC Raw Water Main on Chino Avenue intersection that would convey the water to the Eastside Water Treatment Facility (EWTF) located at 7537 Schaeffer Avenue, Ontario, CA for treatment and distribution back into the system.

