



**Sierra Avenue 8-inch Water Main
Replacement
Marygold Mutual Water Company
Bloomington, CA**



Project Type
Domestic Water Pipeline

Project References
Justin Brokaw
General Manager
Marygold Mutual Water Company
(909) 877-0516

This project was a result of the City of Fontana doing some street improvement work at the intersection of Sierra Avenue and Valley Boulevard. The City was in the process of redoing the curb return at the north east intersection of the street when the existing 8-inch steel water main was encountered at a shallow depth. The existing water main needed to be relocated from its current alignment to allow for the street improvements to proceed without interruption.

Steven Andrews Engineering was obtained by Marygold Mutual Water Company to oversee and inspect the design built of approximately 850 lineal feet of 8-inch concrete mortar lined and coated welded steel pipe. The project was constructed as an Emergency Project and construction activities were limited to night work to minimize disruption to City traffic and allow for the street improvement to proceed during the day.

