



**Clara Street Water Main Replacement
Tract 180 Water Company
Cudahy, CA**



**Tract 180
Water Company**

Project Type

Domestic Water Pipeline Conveyance

Project References

Mr. George Perez, President
Tract 180 Water Company
(323) 771-6682

This Facility replaced the Companies existing domestic water distribution pipelines located on both sides of the street that are outside street right of ways that reached their useful life.

Steven Andrews Engineering prepared construction drawings and specifications for the installation of approximately 4,678 feet of 8-inch C900 PVC water main placed within existing street right of way. The alignment started at the intersection of Atlantic Avenue and continued East to River Road.

The project included the abandonment of existing 6-inch and 8-inch steel water mains located outside of street right of way and relocation of existing water meters to be with in street right of way, inline valves, fire hydrant connections, water sampling stations, thrust blocks, speed bump replacement, traffic control, pavement replacement, and street stripping per the City of Cudahy Street Guidelines and Standards.

